

View Online at <https://aerobasegroup.com/nsn/6635-01-344-6403>

Special Features:

X-ray tube head is gas insulated with high voltage generated in head output 150/160 kv continuously variable. Controls are kv control adjust, x-ray tube current, ma control, line power circuit breaker, safety key switch & timer control; key switch enables/disables power supply to control unit & restricts operation to authorized personnel; timer controls-reset switch, timer preset switch. Timer setting from 0.1 to 99.9 min. In 0.1 min. Steps; indicators/meters-power on light glows green when on, x-ray on light glows red when x-ray switch closed. Kv meter indicates voltage applied to tube head. Ma meter indicates tube current; closed self-contained cooling unit provides cooling up to 50 feet above the unit & provided with twin 50 feet hoses with quick disconnects connections

Shelf Life:

N/a

Unit Of Measure:

--

Demilitarization:

Yes - demil/mli

Fiig:

A509j0